



- Contractors must check all dimensions on site. Only figured dimensions are to be worked from. Discrepancies must be reported to the Architect or Engineer before proceeding. © This drawing is copyright
- Reproduced from OS Sitemap © by permission of Ordnance Survey® on behalf of The Controller of Her Majesty's Stationary Office. © Crown copyright 2008. All rights reserved. Licence number 100007126.

**Car Tracking (Plot 19)**



**4 Wheel Drive Car**  
 Overall Length 16.093m  
 Overall Width 6.591m  
 Overall Body Height 6.146m  
 Min Body Ground Clearance 0.877m  
 Max Track Width 5.961m  
 Lock-to-lock time 4.00s  
 Curb to Curb Turning Radius 18.783m

**Delivery Vehicle Tracking**



**FTA Design LG Rigid Vehicle**  
 Overall Length 7.170m  
 Overall Width 2.300m  
 Overall Body Height 3.580m  
 Min Body Ground Clearance 0.375m  
 Track Width 2.120m  
 Lock-to-lock time 3.00s  
 Curb to Curb Turning Radius 7.000m



Revision	Description	Drawn	Checked	Date
Preliminary	Information	Tender	Construction	As Built

**Woods Hardwick**  
 Architects, Engineers and Development Consultants

Title: Land off Hillfoot Road Shillington  
 Details: Additional Tracking (Service/Delivery Vehicle and Car tracking for plot 14)  
 Scale: 1:500@A1 Date: July 2018 Drawn: CM Chk: GS

15-17 Goldington Road  
 Bedford MK40 3NH  
 United Kingdom  
 T. +44 (0)1234 288862  
 F. +44 (0)1234 353034  
 mail@woodshardwick.com  
 www.woodshardwick.com